

U. S. DEPARTMENT OF COMMERCE

BUILDING
MATERIALS
AND
STRUCTURES

REPORT BMS38

Structural Properties of Two
“Dunstone” Wall Constructions
Sponsored by the
W. E. Dunn Manufacturing Co.

by

HERBERT L. WHITEMORE,
AMBROSE H. STANG, *and*
DOUGLAS E. PARSONS

NATIONAL
BUREAU OF STANDARDS

The program of research on building materials and structures, carried on by the National Bureau of Standards, was undertaken with the assistance of the Central Housing Committee, an informal organization of Government agencies concerned with housing construction and finance, which is cooperating in the investigations through a subcommittee of principal technical assistants.

CENTRAL HOUSING COMMITTEE
SUBCOMMITTEE ON TECHNICAL RESEARCH

WALTER JUNGE, *Chairman*.
Federal Housing Administration.

A. C. SHIRE, *Vice Chairman*.
United States Housing Authority.

STERLING R. MARCH, *Secretary*.

ALBERT G. BEAR,
Veterans' Administration.
PIERRE BLOUKE,
Federal Home Loan Bank Board
(Federal Loan Agency).
CARROLL W. CHAMBERLAIN,
Public Buildings Administration (Federal Works Agency).
JOSEPH M. DALLAVALLE,
Public Health Service (Federal Security Agency).
JOHN DONOVAN,
Farm Security Administration (Agriculture).

GEORGE E. KNOX,
Yards and Docks (Navy).
VINCENT B. PHELAN,
National Bureau of Standards (Commerce).
EDWARD A. POYNTON,
Office of Indian Affairs (Interior).
GEORGE W. TRAYER,
Forest Service (Agriculture).
ELSMERE J. WALTERS,
Construction Division (War).

CHAIRMEN OF SECTIONS

<i>Specifications</i>	<i>Materials</i>	<i>Maintenance</i>
CARROLL W. CHAMBERLAIN	ELSMERE J. WALTERS	JOHN H. SCHAEFER
<i>Mechanical Equipment</i>		<i>Methods and Practices</i>
ROBERT K. THULMAN		

NATIONAL BUREAU OF STANDARDS

STAFF COMMITTEE ON ADMINISTRATION AND COORDINATION

HUGH L. DRYDEN, *Chairman*.

Mechanics and Sound.

PHAON H. BATES,
Clay and Silicate Products.
HOBART C. DICKINSON,
Heat and Power.
WARREN E. EMLEY,
Organic and Fibrous Materials.

GUSTAV E. F. LUNDELL,
Chemistry.
ADDAMS S. McALLISTER,
Codes and Specifications.
HENRY S. RAWDON,
Metallurgy.

The Forest Products Laboratory of the United States Department of Agriculture is cooperating with both committees on investigations of wood constructions.

[For list of BMS publications and how to purchase, see cover page III.]

UNITED STATES DEPARTMENT OF COMMERCE • Harry L. Hopkins, Secretary

NATIONAL BUREAU OF STANDARDS • Lyman J. Briggs, Director

BUILDING MATERIALS *and* STRUCTURES

REPORT BMS38

Structural Properties of Two "Dunstone" Wall Constructions
Sponsored by the
W. E. Dunn Manufacturing Co.

by HERBERT L. WHITTEMORE, AMBROSE H. STANG,
and DOUGLAS E. PARSONS



ISSUED FEBRUARY 7, 1940

The National Bureau of Standards is a fact-finding organization; it does not "approve" any particular material or method of construction. The technical findings in this series of reports are to be construed accordingly.

UNITED STATES GOVERNMENT PRINTING OFFICE • WASHINGTON • 1940

FOR SALE BY THE SUPERINTENDENT OF DOCUMENTS, WASHINGTON, D. C. • PRICE 10 CENTS

Foreword

This report is one of a series issued by the National Bureau of Standards on the structural properties of constructions intended for low-cost houses and apartments. These constructions were sponsored by industrial organizations within the building industry advocating and promoting their use. The sponsor built and submitted the specimens described in this report for participation in the program outlined in BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions. The sponsor, therefore, is responsible for the design of the constructions and for the description of the materials and of the method of fabrication. The Bureau is responsible for the method of testing and for the test results.

This report covers only the load-deformation relations and strength of the structural elements of a house when subjected to compressive, transverse, impact, concentrated, and racking loads by standardized methods simulating the loads to which the element would be subjected in actual service. It may be feasible later to determine the heat transmission at ordinary temperatures and the fire resistance of these same constructions.

The National Bureau of Standards does not "approve" a construction, nor does it express an opinion as to the merits of a construction, for the reasons given in reports BMS1 and BMS2. The technical facts presented in this series provide the basic data from which architects and engineers can determine whether a construction meets desired performance requirements.

LYMAN J. BRIGGS, *Director.*

Structural Properties of Two "Dunstone" Wall Constructions

Sponsored by the W. E. Dunn Manufacturing Co.

by HERBERT L. WHITTEMORE, AMBROSE H. STANG, and DOUGLAS E. PARSONS

CONTENTS

	Page		Page
Foreword.....	ii	IV. Wall <i>CF</i> —Continued.	
I. Introduction.....	1	6. Racking load.....	8
II. Sponsor and product.....	2	V. Wall <i>CG</i>	8
III. Specimens and tests.....	2	1. Description.....	8
IV. Wall <i>CF</i>	3	(a) Four-foot wall specimens.....	8
1. Description.....	3	(b) Eight-foot wall specimens.....	10
(a) Four-foot wall specimens.....	3	(c) Fabrication data.....	10
(b) Eight-foot wall specimens.....	5	2. Compressive load.....	10
(c) Fabrication data.....	5	3. Transverse load.....	10
2. Compressive load.....	5	4. Concentrated load.....	11
3. Transverse load.....	6	5. Impact load.....	11
4. Concentrated load.....	7	6. Racking load.....	12
5. Impact load.....	7	VI. Sponsor's comments.....	13

ABSTRACT

For the program on the determination of the structural properties of low-cost house constructions the W. E. Dunn Manufacturing Co. submitted 24 specimens representing 2 designs of their "Dunstone" constructions for walls.

The specimens were subjected to compressive, transverse, concentrated, impact, and racking loads. For each of these loads three like specimens were tested. The deformation under load and the set after the load was removed were measured for uniform increments of load, except for concentrated loads, for which the set only was determined. The results are presented in graphs and in a table.

I. INTRODUCTION

In order to provide technical facts on the performance of constructions which might be used in low-cost houses, to discover promising new constructions, and ultimately to determine the properties necessary for acceptable performance in actual service, the National Bureau of Standards has invited the cooperation of the building industry in a program of research on building materials and structures suitable for low-cost houses and apartments. The objectives of this program are described in report BMS1, Research on Building Materials and Structures for Use in Low-Cost Housing, and that part of the program relating to struc-

tural properties in report BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions.

Masonry constructions and wood constructions of types which have been extensively used in this country for houses were included in the program because their behavior under widely different service conditions is known to builders and the public. The reports on these constructions are BMS5, Structural Properties of Six Masonry Wall Constructions, and BMS25, Structural Properties of Conventional Wood-Frame Constructions for Walls, Partitions, Floors, and Roofs. The masonry specimens were built by the Masonry Construction Section of this Bureau, and the wood-frame specimens were built and tested by the Forest Products Laboratory at Madison, Wis.

The present report describes the structural properties of two wall constructions sponsored by one of the manufacturers in the building industry. The specimens were subjected to compressive, transverse, concentrated, impact, and racking loads, simulating loads to which the walls of a house are subjected. In actual service, compressive loads on a wall are produced by the weight of the roof, second floor and second-story walls if any, furniture and occupants, and snow and wind loads on the roof. Transverse loads on a wall are produced

by the wind, concentrated and impact loads by furniture or accidental contact with heavy objects, and racking loads by the action of the wind on adjoining walls.

The deformation and set under each increment of load were measured, because the suitability of a wall construction depends in part on its resistance to deformation under load and whether it returns to its original size and shape when the load is removed.

II. SPONSOR AND PRODUCT

The specimens were submitted by the W. E. Dunn Manufacturing Co., Holland, Mich., and represented two wall constructions sponsored by this company and marketed under the trade name "Dunstone." The "Dunstone" concrete blocks were made under franchise by the Silver Hill Brick Corporation, Washington, D. C. The blocks were laid to form a hollow wall. The specimens were built with cement-lime mortar.

III. SPECIMENS AND TESTS

The concrete blocks used as headers, which tied the two faces of the wall together, were vertical for one construction and horizontal for the other. The wall construction with vertical headers was assigned the symbol *CF*; the construction with horizontal headers, the symbol *CG*; and the specimens were assigned the designations given in table 1.

TABLE 1.—*Specimen designations, walls CF and CG*

Specimen designation	Load	Load applied
<i>C1, C2, C3</i>	Compressive.....	Upper end.
<i>T1, T2, T3</i>	Transverse.....	Either face.
<i>P1, P2, P3</i> *.....	Concentrated.....	Do.
<i>I1, I2, I3</i>	Impact.....	Do.
<i>R1, R2, R3</i>	Racking.....	Near upper end.

* These specimens were undamaged portions of the transverse specimens.

The specimens were tested in accordance with BMS2, Methods of Determining the Structural Properties of Low-Cost House Constructions, which also gives the requirements for the specimens and describes the presentation of the results of the tests, particularly the load-deformation graphs.

For the transverse and impact loads, only three specimens were built, because the speci-

mens were symmetrical about a vertical plane midway between the faces; and the results for transverse and impact loads applied to one face should be identical with those obtained by applying the loads to the other face. The concentrated loads were applied to only three specimens, because the inside and outside faces of the specimens were similar.

The compressive loads were applied over the entire thickness of the walls along a line distant from one face by one-third this thickness. The shortenings and sets were measured by means of compressometers attached to the steel loading plates through which the load was applied to the specimen, not attached to the specimen as described in BMS2.

Measurements of the lateral deflections under compressive loads and deflections under transverse loads were made with a deflectometer of fixed gage length. This deflectometer consists of a light (duralumin) tubular frame having a leg at one end and a hinged plate at the other. The distance between points of support was 7 ft 6 in. A dial micrometer was attached to the deflectometer at midlength. The micrometer was graduated to 0.001 in., and the readings were recorded to the nearest tenth of a division. The deflectometer was attached to the specimen in a vertical position by clamping the hinged plate to the upper end of one face. There were two deflectometers on each specimen, one near each edge. This method of measurement was used instead of the taut-wire and mirror-scale method, as described in BMS2.

The deformations under racking loads were measured by a dial micrometer which was fastened to one end of a rigid right angle built up with a steel channel and a steel angle braced to form a rigid connection. In use, this deformeter was attached to the specimen by resting the channel along the top of the specimen. Two pins driven through this channel into the top of the specimen prevented relative motion between them. The steel angle was then in a suspended vertical position in the plane of the specimen with the dial at its lowest point and the spindle of the dial bearing directly on the specimen. This deformeter was used instead of the system of taut wires and mirror scales, as described in BMS2.

The tests were begun March 6, 1939, and completed March 20, 1939. The specimens were tested 28 days after they were built. The sponsor was notified when the tests would be started but found it impossible to have a representative present.

IV. WALL CF

1. DESCRIPTION

(a) Four-Foot Wall Specimens

The 4-ft wall specimens with vertical headers were 8 ft 5¼ in. high, 4 ft 2¼ in. wide, and 8⅝ in. thick, and had 12 courses of blocks. The blocks formed an all-rolok in Flemish bond wall, as shown in figure 1. Each course con-




FIGURE 1.—Four-foot wall specimen CF.

A, 1-core block as stretcher; B, 3-core block as stretcher; C, 2-core block as bonding header; D, mortar 2 in. thick; E, concrete fill; F, expanded metal; G, 1-core block for end of concrete form.

sisted of 1-core blocks, A, and 3-core blocks, B, as stretchers with 2-core blocks, C, as bonding headers. The details of the blocks are shown in figures 2 and 3. The bed joints and head joints were completely filled with mortar and were cut flush with the surface of the wall.




FIGURE 2.—“Dunstone” concrete blocks.
1-core and 2-core blocks.




FIGURE 3.—“Dunstone” concrete block.
3-core block.

The space between the blocks of the first course was filled with mortar, D, to a height of about 2 in. above the bottom of the wall to support the first course during construction. The top course was filled with concrete, E. The bottom form for the concrete was made by placing a length of expanded-metal corner bead, hammered flat, F, in the bed joint and filling the openings in the expanded metal with mortar. Two 1-core blocks, G, laid in the space between the blocks of the top course served as the end forms for the concrete. The concrete was poured on the day following the completion of the specimen.



FIGURE 4.—Wall specimen CF-C1 under compressive load.

The price of this construction in Washington, D. C., as of July 1937, was \$0.20/ft².

Concrete blocks.—The materials for the blocks were portland cement and washed bank sand (passed $\frac{1}{4}$ -in. sieve). The blocks were made by the Silver Hill Brick Corporation in the proportions of 8 parts of sand to 1 part of portland cement by volume. The blocks were made on a standard Dunbrik-Dunstone machine manufactured by the W. E. Dunn Manufacturing Co.

The physical properties of the concrete

blocks, determined by the Masonry Construction Section of the National Bureau of Standards, in accordance with the ASTM Standard C 90-36,¹ are given in table 2.

TABLE 2.—Physical properties of the concrete blocks, walls CF and CG

Block	Compressive strength, ^a gross area	Water absorption, 24-hr cold immersion		Dry weight	
		By weight	Per cubic foot of concrete	Per block	Per cubic foot of concrete
	lb/in. ²	Percent	lb	lb	lb
1-core	1,330	11.0	12.7	3.81	116
2-core	2,060	6.2	9.3	9.78	129
3-core	1,730	7.4	9.7	13.90	125

^a Load applied in direction of longer dimension of core.

Mortar.—The materials for the mortar were Medusa Cement Co.'s "Medusa" portland cement, lime putty made by slaking Standard Lime and Stone Co.'s "Washington" powdered quicklime, and Potomac River building sand.

The mortar was 1 part of cement, 0.42 part of hydrated lime, and 5.1 parts of dry sand, by weight. The proportions by volume were 1 part of cement, 1 part of hydrated lime, and 6 parts of loose damp sand; assuming that portland cement weighs 94 lb/ft³, dry hydrated lime 40 lb/ft³, and that 80 lb of dry sand is equivalent to 1 ft³ of loose damp sand. The materials for each batch were measured by weight and mixed for not less than 2 minutes in a batch mixer having a capacity of $\frac{2}{3}$ ft³. The amount of water added to the mortar was adjusted to the satisfaction of the mason.

The following properties of the mortar materials and of the mortar and concrete were determined by the Masonry Construction Section. The cement complied with the requirements of Federal Specification SS-C-191a, Cement; Portland, for fineness, soundness, time of setting, and tensile strength. The lime putty contained 40 to 45 percent of dry hydrate, by weight, and had a plasticity of over 600, measured in accordance with Federal Specification SS-L-351, Lime; Hydrated (for) Structural Purposes. The sieve analysis of the sand in the mortar is given in table 3.

¹ ASTM Standards, pt. 2, 168-171 (1936).

TABLE 3.—Sieve analysis of the sand in mortar, walls CF and CG

U. S. Standard Sieve number	Passing, by weight
	Percent
8	100
16	98
30	81
50	23
100	3

The average water content of the mortar was 23.9 percent by weight of the dry materials. Samples were taken from at least one batch of mortar for each wall specimen, the flow determined in accordance with Federal Specification SS-C-181b, Cement; Masonry, and six 2-in. cubes made. Three cubes were stored in water at 70° F and three in air near the wall specimen. The compressive strength of each cube was determined on the day the corresponding wall specimen was tested. The physical properties of the mortar are given in table 4.

TABLE 4.—Physical properties of the mortar and of the concrete, wall CF

[The compressive strengths were determined on the day the corresponding wall specimens were tested]

Specimen	Mortar			Concrete, compressive strength
	Flow	Compressive strength		
		Air stor- age	Water storage	
	<i>Percent</i>	<i>lb/in.²</i>	<i>lb/in.²</i>	<i>lb/in.²</i>
<i>C1</i>	109	550	740	2,790
<i>C2</i>	108	595	720	3,970
<i>C3</i>	106	580	760	2,830
<i>T1</i>	102	755	745	3,250
<i>T2</i>	108	495	660	2,700
<i>T3</i>	109	470	640	2,700
<i>I1</i>	107	545	745	2,790
<i>I2</i>	106	600	765	3,970
<i>I3</i>	108	590	715	3,970
<i>R1</i>	}	110	490	645
		105	540	680
		108	590	595
<i>R2</i>	}	113	630	545
		120	655	600
<i>R3</i>		114	665	770
Average	109	580	690	3,130

Concrete.—The materials for the concrete fill in the top course of the wall were Medusa Cement Co.'s "Medusa" portland cement, Potomac River concrete sand, and Potomac River gravel (maximum size ¾ in.).

The concrete was 1 part of cement, 2.1 parts of dry sand, and 3.7 parts of dry gravel, by weight. The proportions by volume were 1 part of cement, 2.5 parts of loose damp sand, and 3.5 parts of gravel.

A 6- by 12-in. cylinder was made by the Masonry Construction Section from the concrete for each wall specimen and stored in air near the specimen. The compressive strength of each cylinder was determined on the day the corresponding wall specimen was tested. The compressive strengths of the concrete cylinders are given in table 4.

Expanded metal.—The expanded metal used for the bottom form of the concrete fill was a galvanized corner bead of expanded metal, 2½ in. on each side, hammered flat. The metal was 0.025 in. thick (No. 24 U. S. Std. Gage). The corner bead weighed 0.21 lb/ft.

(b) Eight-Foot Wall Specimens

The 8-ft wall specimens were 8 ft 5¼ in. high, 8 ft ⅝ in. wide, and 8⅝ in. thick, having 12 courses of blocks. The specimens were similar to the 4-ft wall specimens.

(c) Fabrication Data

The fabrication data, determined by the Masonry Construction Section, are given in table 5.

TABLE 5.—Fabrication data, walls CF and CG

[The values per square foot were computed, using the face area of the specimens]

Construction symbol	CF	CG
Thickness of bed joints, in	0.37	0.36
Thickness of head joints, in	.40	.39
1-core blocks, number/ft ²	.68	
2-core blocks, number/ft ²	1.02	
3-core blocks, number/ft ²	2.04	3.08
Mortar materials:		
Cement, lb/ft ²	1.14	1.18
Lime, dry hydrate, lb/ft ²	0.477	0.495
Sand, dry, lb/ft ²	5.78	6.02
Mason's time, hr/ft ²	0.073	0.082

2. COMPRESSIVE LOAD

Wall specimen CF-C1 under compressive load is shown in figure 4. The results for wall specimens CF-C1, C2, and C3 are shown in table 6 and in figures 5 and 6.

TABLE 6.—Structural properties of "Dunstone" wall constructions CF and CG

[Weight: Wall CF, 52.6 lb/ft²; wall CG, 54.8 lb/ft², based on the face area]

Construction symbol	Load									
	Compressive ^a		Transverse ^b		Concentrated		Impact ^c		Racking	
	Specimen	Maximum load	Specimen	Maximum load	Specimen	Maximum load	Specimen	Maximum height of drop	Specimen	Maximum load
		^e Kips/ft		lb/ft ²		lb		ft		^e Kips/ft
CF	C1	38.9	T1	36.0	P1	^d 1,000	I1	2.5	R1	1.81
	C2	40.2	T2	29.1	P2	^d 1,000	I2	2.5	R2	1.93
	C3	42.7	T3	26.0	P3	^d 1,000	I3	3.0	R3	2.28
Average		40.6		30.4		^d 1,000		2.7		2.01
CG	C1	35.9	T1	24.0	P1	^d 1,000	I1	2.0	R1	2.00
	C2	38.3	T2	(^e)	P2	^d 1,000	I2	2.0	R2	2.18
	C3	38.7	T3	26.0	P3	^d 1,000	I3	2.0	R3	3.56
Average		37.6		25.0		^d 1,000		2.0		2.58

^a The compressive loads were applied 2.71 in. from one face of the specimen on wall CF and 2.69 in. from one face of the specimen on wall CG.
^b Span 7 ft 6 in.

^c A kip is 1,000 lb.

^d Test discontinued. Specimen did not fail.

^e This specimen had an initial crack.




FIGURE 5.—Compressive load on wall CF.

Load-shortening (open circles) and load-set (solid circles) results for specimens CF-C1, C2, and C3. The load was applied one-third the thickness (2.71 in.) from one face. The loads are in kips per foot of actual width of specimen.

At loads of 32.0 and 39.6 kips/ft stretchers, at one edge on the face nearer the load line and near the top, cracked vertically in specimens C1 and C2, respectively. Specimen C1 collapsed at the maximum load, failing by cracking of the stretchers on the inside face near the top. Specimen C2 failed by breaking of all the headers midway between the two faces. Specimen

C3 failed by breaking of the headers at one edge near the top.

3. TRANSVERSE LOAD

The results of the transverse load are shown in table 6 and in figure 7 for wall specimens CF-T1, T2, and T3.




FIGURE 6.—Compressive load on wall CF.

Load-lateral deflection (open circles) and load-lateral set (solid circles) results for specimens CF-C1, C2, and C3. The load was applied one-third the thickness (2.71 in.) from one face. The loads are in kips per foot of actual width of specimen. The deflections and sets are for a gage length of 7 ft 6 in., the gage length of the deflectometers.




FIGURE 7.—Transverse load on wall CF.

Load-deflection (open circles) and load-set (solid circles) results for specimens CF-T1, T2, and T3 on the span 7 ft 6 in. The deflections and sets are for a gage length of 7 ft 6 in., the gage length of the deflectometers.

Each of the specimens T1, T2, and T3 failed by rupture of the bond between the mortar and the concrete blocks at a bed joint between loading rollers.

4. CONCENTRATED LOAD

The results of the concentrated load on wall specimens CF-P1, P2, and P3 are shown in table 6 and in figure 8.

Wall specimens CF-P1, P2, and P3, loaded on a stretcher block near the center of the wall, showed no measurable indentation after a load of 1,000 lb had been applied and released.

5. IMPACT LOAD

The results of the impact load on wall specimens CF-I1, I2, and I3 are shown in table 6 and in figure 9.

In each of the specimens I1, I2, and I3 a bond crack appeared in a bed joint near mid-span on the face not struck at a height of drop of 1.5 ft. In each case failure occurred at this bond crack, which extended to the face struck.

Wall specimen CF-I1 during the impact test is shown in figure 10.




FIGURE 8.—Concentrated load on wall CF.

Load-indentation results for specimens CF-P1, P2, and P3.




FIGURE 9.—Impact load on wall CF.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens CF-I1, I2, and I3 on the span 7 ft 6 in.

6. RACKING LOAD

The results of the racking load on wall specimens *CF-R1*, *R2*, and *R3* are shown in table 6 and in figure 11.

The deformations and sets shown in figure 11 were computed from the deformer readings. The gage length of the deformers was 7 ft 2 in.

Stepwise cracks through the bed and head joints appeared in specimens *R1* and *R2* at a load of 1.5 kips/ft and in *R3* at a load of 1.2 kips/ft. Each of the specimens failed by rupture of the cracked bed and head joints approxi-

mately along a diagonal between the point of application of the load and the stop.

V. WALL CG

1. DESCRIPTION

(a) *Four-Foot Wall Specimens*

The 4-ft wall specimens with horizontal headers were 8 ft $3\frac{3}{4}$ in. high, 4 ft $2\frac{3}{4}$ in. wide, and $8\frac{1}{16}$ in. thick, and had 18 courses of blocks. The blocks formed an all-rolok wall, every other course being a header course with the




FIGURE 10.—Wall specimen *CF-II* during the impact test.

blocks laid flat, as shown in figure 12. Three-core blocks (shown in fig. 3) laid on edge, *A*, were used in the stretcher courses and the same size blocks laid flat, *B*, were used in the header courses. Blocks, *C*, 1½-core, were used to stagger the head joints. The bed joints and the




FIGURE 11.—Racking load on wall *CF*.

Load-deformation (open circles) and load-set (solid circles) results for specimens *CF*, *R1*, *R2*, and *R3*. The loads are in kips per foot of actual width of specimen.

head joints were completely filled with mortar and were cut flush with the surface of the wall. After the first course was laid, about 2 in. of mortar, *D*, was spread in the cavity to support the blocks laterally. The uppermost stretcher course was filled with concrete, *E*. A 1-core block, *F* (shown in fig. 2), laid inside this course, served as the end form for the concrete. The top header course was placed after the concrete was poured.

The price of this construction in Washington, D. C., as of July 1937, was \$0.20/ft².

The concrete blocks, the mortar, and the concrete fill had the same proportions in wall *CG* as in wall *CF* and were made, sampled, and tested using the same methods.

For wall *CG* the average water content of the mortar was 24.0 percent by weight of the dry materials. The physical properties of the mortar and of the concrete are given in table 7.

TABLE 7.—Physical properties of the mortar and of the concrete, wall *CG*

[The compressive strengths were determined on the day the corresponding wall specimens were tested]

Specimen	Mortar			
	Flow	Compressive strength		Concrete, compressive strength
		Air storage	Water storage	
	Percent	lb/in. ²	lb/in. ²	lb/in. ²
C1	109	555	715	3,390
C2	108	530	750	4,020
C3	107	680	710	4,110
T1	108	470	730	4,020
T2	107	600	730	3,540
T3	108	585	665	3,250
I1	108	525	740	2,830
I2	108	570	715	3,390
I3	106	610	765	4,020
R1	{ 108	585	705	3,290
	{ 116	495	630	3,290
R2	{ 114	590	700	3,330
	{ 112	550	700	3,330
R3	{ 113	490	675	3,180
	{ 114	555	720	3,180
Average	109	560	710	3,480




FIGURE 12.—Four-foot wall specimen *CG*.

A, 3-core block as stretcher; *B*, 3-core block as header; *C*, 1½-core block; *D*, mortar 2 in. thick; *E*, concrete fill; *F*, 1-core block for end of concrete form.




FIGURE 13.—Compressive load on wall CG.

Load-shortening (open circles) and load-set (solid circles) results for specimens CG-C1, C2, and C3. The loads were applied one-third the thickness (2.69 in.) from one face. The loads are in kips per foot of actual width of specimen.




FIGURE 14.—Compressive load on wall CG.

Load-lateral deflection (open circles) and load-lateral set (solid circles) results for specimens CG-C1, C2, and C3. The load was applied one-third the thickness (2.69 in.) from one face. The loads are in kips per foot of actual width of specimen. The deflections and sets are for a gage length of 7 ft 6 in., the gage length of the deflectometers.

(b) Eight-Foot Wall Specimens

The 8-ft wall specimens were 8 ft $3\frac{3}{4}$ in. high, 8 ft $5\frac{1}{2}$ in. wide, and $8\frac{1}{16}$ in. thick. The specimens were similar to the 4-ft wall specimens.

(c) Fabrication Data

The fabrication data, determined by the Masonry Construction Section, are given in table 5.

2. COMPRESSIVE LOAD

The results of the compressive load on wall specimens CG-C1, C2, and C3 are shown in table 6 and in figures 13 and 14.

In specimen C1, a block on the face nearer the load line at one end near midheight crushed at a load of 34.5 kips/ft. Failure occurred by the crushing of blocks and mortar in the two adjacent courses on the face nearer the load line and near midheight. Specimens C2 and C3 failed by breaking of the headers at the inner surfaces of both faces, each header breaking in two places. Specimen C2, at the maximum load, collapsed suddenly without warning.

3. TRANSVERSE LOAD

Wall specimen CG-T2 under transverse load is shown in figure 15.

The results of the transverse load on wall specimens CG-T1, T2, and T3 are shown in table 6 and in figure 16.

After specimen T2 had been set in place for the transverse test, but before a load had been applied, it was noticed that a bond crack in the bed joint below the fourteenth course existed in both faces. This crack was probably caused by moving the specimen into position for testing. The maximum load on specimen T2 was 10.3 lb/ft², at which load the initial crack widened.

In specimen T3, a crack in the bond between the mortar and the blocks at a bed joint appeared at a load of 20 lb/ft².

At the maximum loads each of the specimens T1, T2, and T3 failed by rupture of the bond between the mortar and the blocks at a bed joint.




FIGURE 15.—Wall specimen CG-T2 under transverse load.

4. CONCENTRATED LOAD

The results of the concentrated load on wall specimens CG-P1, P2, and P3 are shown in table 6 and in figure 17.

There was no measurable indentation for any of the specimens after a load of 1,000 lb had been applied and released.

5. IMPACT LOAD

The results of the impact load on wall specimens CG-I1, I2, and I3 are shown in table 6 and in figure 18.




FIGURE 16.—Transverse load on wall CG.

Load-deflection (open circles) and load-set (solid circles) results for specimens CG-T1, T2, and T3 on the span 7 ft 6 in. The deflections and sets are for a gage length of 7 ft 6 in., the gage length of the deflectionometers.




FIGURE 17.—Concentrated load on wall CG.

Load-indentation results for specimens CG-P1, P2, and P3.




FIGURE 18.—Impact load on wall CG.

Height of drop-deflection (open circles) and height of drop-set (solid circles) results for specimens CG-I1, I2, and I3 on the span 7 ft 6 in.

A bond crack appeared in a bed joint near midspan on the face not struck in specimens CG-I1, I2, and I3 at a height of drop of 1.0, 1.5, and 1.0 ft, respectively. In each case, at failure, this bond crack extended to the face struck.

6. RACKING LOAD

Wall specimen CG-R2 under racking load is shown in figure 19. The results for wall specimens CG-R1, R2, and R3 are shown in table 6 and in figure 20.

The deformations and sets shown in figure 20 were computed from the deformer readings. The gage length of the deformers was 6 ft 7 in.

Each of the specimens failed by rupture of the bed and head joints in stepwise cracks approximately along a diagonal between the point of application of load and the stop. In addition, in each case the concrete blocks at the toe cracked diagonally at the maximum load.




FIGURE 19.—Wall specimen CG-R2 under racking load.

VI. SPONSOR'S COMMENTS

Reinforced-concrete pilasters or columns are formed in the space between the facing and backing by inserting stops at the desired location and placing reinforcing steel and concrete




FIGURE 20.—Racking load on wall CG.

Load-deformation (open circles) and load-set (solid circles) results for specimens CG-R1, R2, and R3. The loads are in kips per foot of actual width of specimen.

in the enclosed space. Beams and lintels are also reinforced concrete, formed in the same manner.

The outside of the wall may be finished with cement paint or may be stuccoed. The inside of the wall may be finished with plaster, consisting of a ½-in. base coat applied directly to the blocks and covered by the usual white

finish. The total cost of these constructions in Washington, D. C., as of July 1937, when weatherproofed with cement paint and plastered on the inside, is \$0.36/ft².

The "Dunstone" blocks are manufactured by 96 individually owned plants in different parts of the country. There are no standardized mixes for the blocks due to the use of local materials. Each plant has tests made by the local testing laboratories to insure compliance with the requirements of the sponsor and of the building codes of different cities.

Many other sizes of "Dunstone" blocks than the three sizes mentioned in this report are available. They may be obtained in a wide range of colors, shades, and textures, offering a permanent colored exterior for the building.


The "Dunstone" blocks may be used for other types of walls than the two described in this report and for veneering frame constructions.

The drawings of the specimens were prepared by E. J. Schell and G. W. Shaw, of the Bureau's Building Practice and Specifications Section, under the supervision of V. B. Phelan.

The structural properties were determined by the Engineering Mechanics Section, under the supervision of H. L. Whittemore and A. H. Stang, and the Masonry Construction Section, under the supervision of D. E. Parsons, with the assistance of the following members of the professional staff: F. Cardile, H. Dollar, M. Dubin, A. H. Easton, A. S. Endler, C. C. Fishburn, C. D. Johnson, A. B. Lanham, P. H. Petersen, A. J. Sussman, and L. R. Sweetman.

WASHINGTON, August 5, 1939.

○



BUILDING MATERIALS AND STRUCTURES REPORTS

On request, the Superintendent of Documents, U. S. Government Printing Office, Washington, D. C., will place your name on a special mailing list to receive notices of new reports in this series as soon as they are issued. There will be no charge for receiving such notices.

An alternative method is to deposit with the Superintendent of Documents the sum of \$5, with the request that the reports be sent to you as soon as issued, and that the cost thereof be charged against your deposit. This will provide for the mailing of the publications without delay. You will be notified when the amount of your deposit has become exhausted.

If 100 copies or more of any report are ordered at one time, a discount of 25 percent is allowed. Send all orders and remittances to the *Superintendent of Documents, U. S. Government Printing Office, Washington, D. C.*

The following publications in this series are now available by purchase from the Superintendent of Documents at the prices indicated:

BMS1	Research on Building Materials and Structures for Use in Low-Cost Housing.....	10¢
BMS2	Methods of Determining the Structural Properties of Low-Cost House Constructions....	10¢
BMS3	Suitability of Fiber Insulating Lath as a Plaster Base.....	10¢
BMS4	Accelerated Aging of Fiber Building Boards.....	10¢
BMS5	Structural Properties of Six Masonry Wall Constructions.....	15¢
BMS6	Survey of Roofing Materials in the Southeastern States.....	15¢
BMS7	Water Permeability of Masonry Walls.....	10¢
BMS8	Methods of Investigation of Surface Treatment for Corrosion Protection of Steel.....	10¢
BMS9	Structural Properties of the Insulated Steel Construction Co.'s "Frameless-Steel" Constructions for Walls, Partitions, Floors, and Roofs.....	10¢
BMS10	Structural Properties of One of the "Keystone Beam Steel Floor" Constructions Sponsored by the H. H. Robertson Co.....	10¢
BMS11	Structural Properties of the Curren Fabrihome Corporation's "Fabrihome" Constructions for Walls and Partitions.....	10¢
BMS12	Structural Properties of "Steelox" Constructions for Walls, Partitions, Floors, and Roofs Sponsored by Steel Buildings, Inc.....	15¢
BMS13	Properties of Some Fiber Building Boards of Current Manufacture.....	10¢
BMS14	Indentation and Recovery of Low-Cost Floor Coverings.....	10¢
BMS15	Structural Properties of "Wheeling Long-Span Steel Floor" Construction Sponsored by the Wheeling Corrugating Co.....	10¢
BMS16	Structural Properties of a "Tilecrete" Floor Construction Sponsored by Tilecrete Floors, Inc.....	10¢
BMS17	Sound Insulation of Wall and Floor Constructions.....	10¢
BMS18	Structural Properties of "Pre-Fab" Constructions for Walls, Partitions, and Floors Sponsored by the Harnischfeger Corporation.....	10¢
BMS19	Preparation and Revision of Building Codes.....	15¢
BMS20	Structural Properties of "Twachtman" Constructions for Walls and Floors Sponsored by Connecticut Pre-Cast Buildings Corporation.....	10¢
BMS21	Structural Properties of a Concrete-Block Cavity-Wall Construction Sponsored by the National Concrete Masonry Association.....	10¢
BMS22	Structural Properties of "Dun-Ti-Stone" Wall Construction Sponsored by the W. E. Dunn Manufacturing Co.....	10¢
BMS23	Structural Properties of a Brick Cavity-Wall Construction Sponsored by the Brick Manufacturers Association of New York, Inc.....	10¢
BMS24	Structural Properties of a Reinforced-Brick Wall Construction and a Brick-Tile Cavity-Wall Construction Sponsored by the Structural Clay Products Institute.....	10¢
BMS25	Structural Properties of Conventional Wood-Frame Constructions for Walls, Partitions, Floors, and Roofs.....	15¢
BMS26	Structural Properties of "Nelson Pre-Cast Concrete Foundation" Wall Construction Sponsored by the Nelson Cement Stone Co., Inc.....	10¢
BMS27	Structural Properties of "Bender Steel Home" Wall Construction Sponsored by The Bender Body Co.....	10¢
BMS28	Backflow Prevention in Over-Rim Water Supplies.....	10¢
BMS29	Survey of Roofing Materials in the Northeastern States.....	10¢
BMS30	Structural Properties of a Wood-Frame Wall Construction Sponsored by the Douglas Fir Plywood Association.....	10¢
BMS31	Structural Properties of "Insulite" Wall and "Insulite" Partition Constructions Sponsored by The Insulite Co.....	15¢
BMS32	Structural Properties of Two Brick-Concrete-Block Wall Constructions and a Concrete-Block Wall Construction Sponsored by the National Concrete Masonry Association.....	10¢
BMS33	Plastic Calking Materials.....	10¢
BMS34	Performance Test of Floor Coverings for Use in Low-Cost Housing: Part 1.....	10¢
BMS35	Stability of Sheathing Papers as Determined by Accelerated Aging.....	10¢
BMS36	Structural Properties of Wood-Frame Wall, Partition, Floor, and Roof Constructions with "Red Stripe" Lath Sponsored by The Weston Paper and Manufacturing Co.....	10¢
BMS38	Structural Properties of Two "Dunstone" Wall Constructions Sponsored by the W. E. Dunn Manufacturing Company.....	10¢

